


# ZX5 Production R0015139 Module B to R0015000B Module C alignment

Alignment process and criteria for module B to C

 Difficulty **Hard**

 Duration **2 hour(s)**

## Contents

Introduction

Step 1 - Quality check

Step 2 - Position Module B

Step 3 - Quality check

Step 4 - Level module B

Step 5 - Finalise X axis position

Step 6 - Set Gripper pin position A

Step 7 - Set Gripper pin position B

Step 8 - Repeat Steps 6 and 7

Step 9 - Set Module B height

Step 10 - Recheck settings

Step 11 - Check gripper clearance

Step 12 - Laser alignment Height

Step 13 - Laser alignment Parallel

Step 14 - Move Gripper

Step 15 - Cast laser to Gripper

Step 16 - Connect Ring mains

Comments

## Introduction

Alignment details and level settings for correct alignment of module B to module C

### Step 1 - Quality check





Before installing module B, module C roller tables should be double checked for correct positioning

1 To do this inspect tables 1, 2,3 and 4 for level as shown.

2 Also inspect alignment with 2 meter straight edge. All rollers should be on the same height and no bump up should be present when moving the straight edge over the table.

3 Ensure fixed table is at same height as rollers

Report any discrepancies to supervisor for correct remedial action




## Step 2 - Position Module B

Position module B into approximate position and use reference points as listed

1 Set Y axis position using Module C gripper and Module B backfences as reference. Visually set approximately gripper just in front of datum rollers

2 Set X axis position by using back of module B and transfer buffer bar as reference. Set bars shown visually parallel and approximately 150mm apart

3 Ensure all 4 adjustment feet and set in levelling pads and touching



---

## Step 3 - Quality check

Before installation a quality check should be performed on Module B datum rollers

Check horizontal and vertical rollers

Use 2 meter straight edge to check alignment of rollers as shown . Tolerance 0.002" /0.05mm . Any discrepancy should be reported to supervisor for suggested remedial action







---

## Step 4 - Level module B

1 Level Y axis using indicated point


2 Level X axis as shown using 2 meter straight edge on horizontal rollers



## Step 5 - Finalise X axis position

1 Move Module C hepco beam to its fully extended position into Module B

2 Adjust position of module B to set gap as shown at 75mm




---

## Step 6 - Set Gripper pin position A

1 With Hepco beam fully extend, move gripper to position shown

2 Insert grip pin jig as shown, and adjust Module B position to set gripper pins to enter jig perfectly



## Step 7 - Set Gripper pin position B

1 Move gripper to position shown

2 Insert grip pin jig as shown, and adjust Module B position to set gripper pins to enter jig perfectly



## Step 8 - Repeat Steps 6 and 7


Move gripper to position A and recheck pin jig setting. Adjust if required to correct. If any adjustments are required, it is vital that the other point is checked after. Continue to adjust and correct until no adjustments are needed and both pin jig positions are correct



## Step 9 - Set Module B height

Use 2 meter straight edge in Module b as shown to extend height out to Module C fixed table

Adjust height of module B to set datum roller heights to be 0.25-0.5mm above fixed cut table on Module C



---



## Step 10 - Recheck settings

Once pin alignment has been set, it is vital all previous settings are checked to ensure they have not been affected

- 1 Check Y and X axis levels
- 2 Check correct gap is still present between Hepco beam and module B  
75mm +-3mm Tolerance

If any adjustments are require, please ensure height between module B and C is rechecked after adjustments are made







---

## Step 11 - Check gripper clearance



Check gripper clearance above Module B datum rollers and cut tables

Move gripper into machining centre . Ensure hepcos beam is fully extended

Check clearance is present minimum 1mm gripper above rollers



Check in all positions through module B

Report any collisions to supervisor




## Step 12 - Laser alignment Height

- 1 Move gripper to point just in front of clamps as shown
- 2 Position laser as shown on horizontal datum rollers
- 3 Project laser onto gripper and mark horizontal line as shown to match laser



## Step 13 - Laser alignment Parallel

- 1 Move gripper to point just in front of clamps as shown
- 2 Position laser as shown on vertical datum rollers
- 3 Project laser onto gripper and mark vertical line as shown to match laser



## Step 14 - Move Gripper

Move gripper to furthest point away from Module B

Ensure hepco beam is also fully retracted from module B



---

## Step 15 - Cast laser to Gripper

Height

1 With laser in position shown, project to gripper at far end of frame. Working on the horizontal line, inspect to achieve difference. Tolerance  $\pm 5\text{mm}$ . Any discrepancy greater than 5mm should be reported to supervisor

Parallel


2 With laser in position shown, project to gripper at far end of frame. Working on the Vertical line, inspect to achieve difference. Tolerance  $\pm 2\text{mm}$ .

Module B can be adjusted to correct this measurement

Move points as shown to correct laser reading

**⚠** ...Adjustment at this point will effect grip pin jig alignment setting. It is vital if aligned of module B is carried out to correct laser point, pin jig settings must be rechecked after. Sometimes it may not be possible to get perfect laser alignment and grip pin alignment. If this occurs, inform supervisor.







## Step 16 - Connect Ring mains

Connect 2 off 12mm red pipes from transfer wire basket to bulkheads at rear of module B. Leave pipes long to allow final trimming on installation

Connect 1 off 12mm blue airpipe from module C into bulkheads at rear of module B. Leave pipe long to allow final trimming on installation

